



CWRA

CRAIG W. RAPP ASSOCIATES LLC

ARCHITECTURE • PLANNING • INTERIORS

118 West St. Clair Street, Indianapolis, Indiana 46204 / Voice 317.423.4999 / Fax 317.423.4996 / Email cwrappassociates@aol.com

ADDENDUM

Addendum No: 1

Date: April 4 , 2022

Trinity Alloys, LLC
Shelbyville, Indiana

Project No: 21002.00

By: Craig W. Rapp, A.I.A.

This addendum is issued this date and becomes a part of the Bid set drawings dated 2-28-2022 & issued 3-22-2022 as provided therein. For consistent bidding, all bidders shall consider the following clarifications.

CLARIFICATIONS:

1. Reminder - Bids are due on April 13, 2022.
2. A. For all interior slab on grade, apply "LIQUI-HARD" Concrete Densifier & Chemical Hardener (or approved equal) as produced by W.R. Meadows and installed per the manufacturer's recommendations
B.. All Control and Construction Joints to be filled with Semirigid Joint Filler Two-component, semirigid, 100 percent solids, aromatic polyurea with a Type A shore durometer hardness range of 90 to 95 per ASTM D 2240.
3. SHEET A-100 - Walls around Electrical & Riser rooms shall be PIP, not CMU.
4. Contractor shall coordinate with Owner provided kitchen appliances.
5. LVP flooring shall be "Armstrong, Prime Harvest, color as selected by Owner.
HARDWOOD
6. Employee toilet room shall fully ADA compliant, standard stainless steel toilet room accessories as manufactured by "Bobrick, Bradley or approved equal. Private office toilet room shall receive similar standard accessories.
7. Full upper and lower kitchen casework shall be based upon white painted birch craftsmen style as manufactured by "Valleywood" or approved equal. Layouts shall coordinate with Owner's appliance.
8. Provide an emergency shower and eyewash station and a mop basin adjacent to door from Employee area into plant and a
9. The 8" thick aluminum Trinity graphic to be mounted on the Pylon for this Pylon, is this supplied by Owner installed by the Contractor.
10. Regarding Sheet M002; AC-1 is a 3-phase unit.