

**ADDENDUM NO. FIVE**

**PROJECT: Johnson County Recycling Center**

**PROJECT NUMBER: 23122**

**DATE OF ADDENDUM: June 6, 2024**



**THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND IS ISSUED IN ACCORDANCE WITH THE INSTRUCTIONS TO BIDDERS. ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY SIGNING THE ADDENDUM ACKNOWLEDGMENT SECTION OF THE BID FORM.**

**Questions:**

Q: The South Exterior Elevation shows a Type 'S3' Awning Window but the Door and Window schedule shows the Type 'S3' Window as being a fixed (non-operable) window  
A: Exterior windows type S3 to be awning windows per exterior elevations

Q: The floor plan shows an interior Type 'S3' Window in Office 'A101.' Are the Type 'S3' Windows Awning Windows or fixed like shown on the schedule?  
A: Exterior to have an awning, window towards the vestibule to have a slider, a window toward garage bays to be fixed

Q: Is Tubelite an approved equal for aluminum storefronts?  
A: yes

Q: Door A105.1 is shown to be 3'-3/4" wide please confirm  
A: the door to be standard 3'-0"x7'-0" door with transom per window schedule

Q: The PEMB buildings do NOT come with epoxy primer, only standard primer. Addendum 2 states that is acceptable, however, addendum 3 seems to indicate that epoxy primer is required?


A: Provide standard primer on the primary and secondary framing

Q: Are the light duty and heavy duty asphalt the same? The plans show they are. Please confirm



TYPICAL ASPHALT SECTION

1.5" HMA SURFACE 9.5mm, ON  
3" HMA INTERMEDIATE 19.0mm, ON  
6" HMA BASE 25.0mm, ON  
8" COMPACTED AGGREGATE #53, ON  
COMPACTED SUBGRADE (SEE DETAIL-THIS SHEET)



HEAVY DUTY ASPHALT SECTION

1.5" HMA SURFACE 9.5mm, ON  
3" HMA INTERMEDIATE 19.0mm, ON  
6" HMA BASE 25.0mm, ON  
8" COMPACTED AGGREGATE #53, ON  
COMPACTED SUBGRADE (SEE DETAIL-THIS SHEET)

A: Yes, provide the paving profile as shown on plans

**Attachments:** None

**End of Addendum 5**